



Proposal

June 12, 2014

Village of Lombard
255 East Wilson Ave
Lombard, IL. 60148

Attention: Matthew H. Lew, P.E.

Location of Work: 22nd & Main (Southwest Quadrant)

Scope of Work:

Furnish labor, equipment, and materials to perform the following work at the above referenced location.

- Remove the existing deteriorated steel mast arm assembly on the southwest quadrant
- Remove the existing damaged concrete foundation on the southwest quadrant.
- Furnish and install a new 30" diameter x 10' concrete foundation.
- Furnish and install a new Valmont steel mast arm assembly & pole (SMAA&P 26') powder coated dark bronze onto the new concrete foundation on the southwest quadrant.
- Furnish and install one (1) new 3-section LED signal head bracket mounted and one (1) new 5-section LED signal head mast arm mounted onto the new steel mast arm assembly.
- Furnish and install new signal cable.
- Reinstall existing signage onto the new steel mast arm pole assembly.
- Make all necessary splices and connections.

Fifteen Thousand Nine Hundred Nineteen Dollars ----- \$ 15,919.00

Note: Meade will not be responsible for any final landscape restoration

Signed: Thomas L. Talbot

Accepted by: [Signature]

Title: Project Manager

Title: Village President

Date: August 21, 2014



Proposal

June 12, 2014

Village of Lombard
255 East Wilson Ave
Lombard, IL. 60148

Attention: Matthew H. Lew, P.E.

Location of Work: Wilson & Westmore (Southwest Quadrant)

Scope of Work:

Furnish labor, equipment, and materials to perform the following work at the above referenced location.

- Remove the existing deteriorated combination steel mast arm assembly on the southwest quadrant
- Furnish and install a new Valmont combination steel mast arm assembly & pole (CSMAA&P 22' w/ 8'LMA @ 31'MH) powder coated dark bronze onto the existing concrete foundation on the southwest quadrant.
- Relocate the existing video detection cameras, street light luminaire, and signage onto the new combination steel mast arm assembly.
- Furnish and install new two (2) new 3-section LED signal heads, two (2) new LED 5-section signal heads, two (2) new 16" LED pedestrian signal heads, two (2) new pushbutton assemblies, new polycarbonate brackets, new astro bracket assemblies and signal cable.
- Furnish and install new new # 10 xlp-use cable and fuse kit for street light.
- Make all necessary splices and connections.

Thirteen Thousand Three Hundred Twenty-Four Dollars--- \$ 13,324.00

Note: Meade will not be responsible for any final landscape restoration

Signed: Thomas H. Talbot

Accepted by: [Signature]

Title: Project Manager

Title: Village President

Date: August 21, 2014



Proposal

June 12, 2014

Village of Lombard
255 East Wilson Ave
Lombard, IL. 60148

Attention: Matthew H. Lew, P.E.

Location of Work: Wilson & Westmore (Northeast Quadrant)

Scope of Work:

Furnish labor, equipment, and materials to perform the following work at the above referenced location.

- Remove the existing deteriorated combination steel mast arm assembly on the northeast quadrant
- Furnish and install a new Valmont combination steel mast arm assembly & pole (CSMAA&P 20' w/ 8'LMA @ 31'MH) powder coated dark bronze onto the existing concrete foundation on the northeast quadrant.
- Relocate the existing traffic signal heads, emergency vehicle pre-emption detector / confirmation beacon, video detection cameras, street light luminaire, and signage onto the new combination steel mast arm assembly.
- Furnish and install new polycarbonate arm brackets and astro brackets onto the existing signal heads.
- Furnish and install new traffic signal cable, new # 10 xlp-use cable and fuse kit for street light.
- Make all necessary splices and connections.

Nine Thousand Four Hundred Dollars ----- \$ 9,400.00

Note: Meade will not be responsible for any final landscape restoration

Signed: Thomas W. Talbot

Accepted by: [Signature]

Title: Project Manager

Title: Village President

Date: August 21, 2014



Proposal

June 12, 2014

Village of Lombard
255 East Wilson Ave
Lombard, IL. 60148

Attention: Matthew H. Lew, P.E.

Location of Work: Jackson & Westmore (Northeast Quadrant)

Scope of Work:

Furnish labor, equipment, and materials to perform the following work at the above referenced location.

- Remove the existing deteriorated combination steel mast arm assembly on the northeast quadrant
- Furnish and install a new Valmont combination steel mast arm assembly & pole (CSMAA&P 22' w/ 8'LMA @ 31'MH) powder coated dark bronze onto the existing concrete foundation on the northeast quadrant.
- Relocate the existing traffic signal heads, pedestrian signals, video detection cameras, street light luminaire, and signage onto the new combination steel mast arm assembly.
- Furnish and install new pedestrian pushbutton, polycarbonate and astro brackets onto the existing signal heads.
- Furnish and install new traffic signal cable, new # 10 xlp-use cable and fuse kit for street light.
- Make all necessary splices and connections.

Nine Thousand Two Hundred Fifty-Seven Dollars ----- \$ 9,257.00

Note: Meade will not be responsible for any final landscape restoration

Signed: Thomas H. Talbot

Accepted by: [Signature]

Title: Project Manager

Title: Village President

Date: August 21, 2014



Proposal

June 12, 2014

Village of Lombard
255 East Wilson Ave
Lombard, IL. 60148

Attention: Matthew H. Lew, P.E.

Location of Work: Jackson & Westmore (Southwest Quadrant)

Scope of Work:

Furnish labor, equipment, and materials to perform the following work at the above referenced location.

- Remove the existing deteriorated combination steel mast arm assembly on the southwest quadrant
- Furnish and install a new Valmont combination steel mast arm assembly & pole (CSMAA&P 22' w/ 8'LMA @ 31'MH) powder coated dark bronze onto the existing concrete foundation on the southwest quadrant.
- Relocate the existing traffic signal heads, pedestrian signals, video detection cameras, street light luminaire, and signage onto the new combination steel mast arm assembly.
- Furnish and install new pedestrian pushbutton, polycarbonate and astro brackets onto the existing signal heads.
- Furnish and install new traffic signal cable, new # 10 xlp-use cable and fuse kit for street light.
- Make all necessary splices and connections.

Nine Thousand Five Hundred Seventy Dollars ----- \$ 9,570.00

Note: Meade will not be responsible for any final landscape restoration

Signed: Thomas D. Talbot

Accepted by: [Signature]

Title: Project Manager

Title: Village President

Date: August 21, 2014



9550 W. 55th Street • Suite A • McCook, IL 60525 • 708-588-2500 • 708-588-2501 Fax

Proposal

June 12, 2014

Village of Lombard
255 East Wilson Ave
Lombard, IL. 60148

JUN 16 2014

Attention: Matthew H. Lew, P.E.

Location of Work: Westmore & Madison (Southeast Quadrant)

Scope of Work:

Furnish labor, equipment, and materials to perform the following work at the above referenced location.

- Remove the existing deteriorated steel mast arm assembly on the southeast quadrant
- Furnish and install a new Valmont steel mast arm assembly & pole (SMAA&P 18') powder coated dark bronze onto the existing concrete foundation on the southeast quadrant.
- Relocate the existing traffic signal head and signage onto the new steel mast arm assembly.
- Furnish and install new astro bracket onto the existing signal head.
- Make all necessary splices and connections.

Six Thousand Three Hundred Fifty Dollars ----- \$ 6,350.00

Note: Meade will not be responsible for any final landscape restoration

Signed: Thomas H. Talbot

Accepted by: [Signature]

Title: Project Manager

Title: Village President

Date: August 21, 2014



Proposal

June 12, 2014

Village of Lombard
255 East Wilson Ave
Lombard, IL. 60148

Attention: Matthew H. Lew, P.E.

Location of Work: Westmore & Madison (Southwest Quadrant)

Scope of Work:

Furnish labor, equipment, and materials to perform the following work at the above referenced location.

- Remove the existing deteriorated combination steel mast arm assembly on the southwest quadrant
- Furnish and install a new Valmont combination steel mast arm assembly & pole (CSMAA&P 18' w/ 8'LMA @ 31'MH) powder coated dark bronze onto the existing concrete foundation on the southwest quadrant.
- Relocate the existing traffic signal heads, emergency vehicle pre-emption detector / confirmation beacon, video detection cameras, street light luminaire, and signage onto the new combination steel mast arm assembly.
- Furnish and install new astro brackets onto the existing signal heads.
- Furnish and install new traffic signal cable, new # 10 xlp-use cable and fuse kit for street light.
- Make all necessary splices and connections.

Nine Thousand Four Hundred Seventy-Seven Dollars ----- \$ 9,477.00

Note: Meade will not be responsible for any final landscape restoration

Signed: Thomas A. Tebbat

Accepted by: [Signature]

Title: Project Manager

Title: Village President

Date: August 21, 2014



9550 W. 55th Street • Suite A • McCook, IL 60525 • 708-588-2500 • 708-588-2501 Fax

Proposal

June 12, 2014

Village of Lombard
255 East Wilson Ave
Lombard, IL. 60148

Attention: Matthew H. Lew, P.E.

Location of Work: Washington & Westmore (Northeast Quadrant)

Scope of Work:

Furnish labor, equipment, and materials to perform the following work at the above referenced location.

- Remove the existing deteriorated combination steel mast arm assembly on the northeast quadrant
- Furnish and install a new Valmont combination steel mast arm assembly & pole (CSMAA&P 18' w/ 8'LMA @ 31'MH) powder coated dark bronze onto the existing concrete foundation on the northeast quadrant.
- Relocate the existing traffic signal heads, pedestrian signals, pedestrian pushbutton, video detection cameras, street light luminaire, and signage onto the new combination steel mast arm assembly.
- Furnish and install new polycarbonate and astro brackets onto the existing signal heads.
- Furnish and install new traffic signal cable, new # 10 xlp-use cable and fuse kit for street light.
- Make all necessary splices and connections.

Nine Thousand Three Hundred Eight Dollars ----- \$ 9,308.00

Note: Meade will not be responsible for any final landscape restoration

Signed: Thomas D. Talbot

Accepted by: [Signature]

Title: Project Manager

Title: Village President

Date: August 21, 2014