

VILLAGE OF LOMBARD CHANGE ORDER

PROJECT NAME: Stormwater Detention Improvements at 641 North Main Street PROJECT NO.: SS-24-05
 LOCATION: 641 North Main Street CHANGE ORDER: 1
 CONTRACTOR: Lima Excavating Contractors DATE: September 3, 2024

DESCRIPTION OF CHANGE ORDER: Raise a buried sanitary manhole, replace storm manhole flat-top, and increase quantity of "NON-SPECIAL WASTE DISPOSAL."

ORIGINAL CONTRACT AMOUNT:		[1]	\$ 1,296,611.50
TOTAL OF PREVIOUS AUTHORIZED CHANGE ORDERS:		[2]	\$ -
CURRENT CONTRACT AMOUNT: ((1)+[2])		[3]	\$ 1,296,611.50
PROPOSED CHANGE ORDER: (PENDING APPROVAL)		[4]	\$ 488,202.50
PROPOSED REVISED CONTRACT AMOUNT: (PENDING APPROVAL) ((3)+[4])		[5]	\$ 1,784,814.00

NET OF ALL CHANGE ORDERS: (PENDING APPROVAL) ((2)+[4]) \$ 488,202.50
 TIME EXTENSION OR REDUCTION: None
 TOTAL CONTRACT TIME: (PENDING APPROVAL) -
 BUDGET ESTIMATE: \$ 2,000,000.00
 ENGINEER'S ESTIMATE: \$ 2,000,000.00

RECOMMENDED FOR ACCEPTANCE :

[Signature] 9/3/2024
 Resident Engineer Date
[Signature] 9/3/24
 Contractor Date
[Signature] 9/3/24
 Village Engineer Date
[Signature] 9/14/2024
 Director of Public Works Date

 Assistant Director of Finance Date

Approved By: _____
 Director of Finance Date
 Approved By: _____
 (<\$10K or 25%) Village Manager Date
 Approved By: [Signature]
 (>\$10K or 25%) Village President Date
 Attest: [Signature]
 Village Clerk Date

It is understood that as part of this change order that the Contractor agrees that all bonds, permits, insurance and guarantees are hereby extended to incorporate this Change Order.

ITEM NO.	ITEM DESCRIPTION	CURRENT QUANTITY	UNIT	UNIT PRICE	REVISED QUANTITY	DIFFERENCE	AMOUNT	DESCRIPTION
AUP001	RAISE EXISTING BURIED SANITARY MANHOLE	0.0	L.SUM	\$ 8,747.50	1.00	1.00	\$ 8,747.50	An existing sanitary manhole was buried within the southbound lanes of Main Street. Village staff requested the Contractor to raise and repair sanitary manhole frame and lid.
AUP002	REMOVE AND REPLACE EXISTING MANHOLE FLAT-TOP	0.0	L.SUM	\$ 11,113.00	1.00	1.00	\$ 11,113.00	An existing storm manhole was found to have a damaged flat top within the intersection of Goebel Drive & Main Street. Village staff requested the Contractor to remove and replace the damaged flat top.
1	NON-SPECIAL WASTE DISPOSAL	100.0	CU YD	\$ 79.38	6,000.00	5,900.00	\$ 468,342.00	After soil samples were taken, the existing soils were classified as "Non-Special Waste." This soil classification results in the Contractor unable to haul and dispose of the material at a CCDD dumping facility. The revised quantity is an estimated quantity based off soil sampling locations and estimated volume calculations.
TOTAL =							\$ 488,202.50	