



December 9, 2016

Brian Jack  
Ying L. Miao  
Village of Lombard  
255 E Wilson Ave. Lombard, IL 60148

**RE: MSI Storm and Sewer Investigation**

Dear Brian and Ying,

RedZone Robotics would like to thank the Village of Lombard for the opportunity to provide a quote for the two inspection projects mentioned below. RedZone will utilize our MSI MD Profiler and Responder assets for the inspection of lines in question. The work is anticipated to take 2 Days. We are ready to schedule the work upon signing of the proposal.

**Project(1)-**

· 750' of 42" RCP storm sewer (located at Charles Ln and RT 53 – this pipe goes into a wet land and would be difficult for traditional CCTV equipment.)

· 4,500' of 24" RCP sanitary sewer (located in backyards of the Foxworth Subdivison from Finley Rd to Valley Rd).

**Project(2)-**

Storm sewer to be inspected for the I/I issue is between the structure PS 400, just east of Fairfield, and the structure JCT303 at Chase Ave. The size of the sewer arranges from 72" to 108" including the trunk sewer and two lateral stubs. The total length of the sewer is about 1,800 linear feet.

	Quantity	Unit of Measure	Unit Price	Total Price
Mobilization	1	L/S	Included	Included
MSI (CCTV, Laser, Sonar)	7,050+	LF	Included	Included
Traffic Control (cones and flags)	1	L/S	Included	Included
Reporting-Includes PACP Database	1	L/S	Included	Included
Total		L/S		\$40,000.00

- Project to include additional footage on Day two (2) if time allows.
- RedZone will provide a credit for this project should the Village elect to execute one of the larger projects proposed on November 10, 2016.



1. INSPECTION SCOPE OF SERVICES


RedZone Robotic Services shall provide all the labor, equipment, and material to provide the scope of work services mentioned above:

REDZONE BUDGET PRICING TO INCLUDE:

- 1.1. RedZone shall provide multiple robotic technologies including conventional CCTV and Solo, trained operating crews, analyst, and the necessary appurtenances to access and collect data for the various size sewers utilizing a combination technologies.
2. Exclusions and Special Conditions
  - 2.1 Others to assist in providing access into interceptor for entry.
  - 2.2 Unusual or unique access manholes, vaults or shafts for deployment that require non-standard means/methods and or equipment for insertion and inspection purposes.
  - 2.3 RedZone excludes all bonds
  - 2.4 RedZone excludes prevailing wages
  - 2.5 RedZone excludes traffic control and permits beyond typical signs and cones.

Thank you again for your consideration.


Sincerely,



Tim Graeb  
Regional Business Development Manager  
RedZone Robotics, Inc.

Acceptance / Terms and Conditions

**Client signature below will be regarded as Acceptance and Notice to Proceed**

Signature:   
Name: Keith Giagnorio  
Title: Village President  
Date: December 15, 2016