



ARTLOW PROPOSAL

170 S. Gary Avenue, Carol Stream, IL 60188, 1(800)5-ARTLOW, (630)653-8111, Fax (630)653-8171

"The Professional Concrete Protectors" ... Serving the Nation Since 1963

Sooner or Later You'll Use ARTLOW SYSTEMS... A Union Contractor

Customer ID: 10795

Proposal ID: 55211

Company: VILLAGE OF LOMBARD

Proposal Date: 7/20/2021

Attn: TOM ELLIS

Proj/Site Name: LOMBARD FIRE STATION

Address: 255 E. WILSON AVENUE

FLUID APPLIED FLOORING

Room/PO Box:

Address: 2020 S. HIGHLAND

City, State, Zip: LOMBARD

IL 60148

Unit / Space:

City, State, Zip: LOMBARD IL

We respectfully submit herewith our proposal for furnishing all labor, equipment, and material for...

PREPARATION

SYSTEM DESCRIPTION (SEE LINE A)

<input type="checkbox"/> Scrape	<input type="checkbox"/> Pressure Wash
<input type="checkbox"/> Edge Grind	<input type="checkbox"/> Shave Master
<input type="checkbox"/> Hand Sweep <input type="checkbox"/> Machine Sweep	<input type="checkbox"/> Propane Burnish
<input type="checkbox"/> Hand Scrub <input type="checkbox"/> Machine Scrub	<input checked="" type="checkbox"/> Shotblast
<input checked="" type="checkbox"/> HTC Grind to Remove:	<input type="checkbox"/> Grit Screen
<input type="checkbox"/> Non-Asbestos Mastic	<input type="checkbox"/> Sand
<input type="checkbox"/> Leveling Compound	<input type="checkbox"/> Solvent Tack
<input checked="" type="checkbox"/> EXISTING QUARTZ FLOORING	<input type="checkbox"/> Tile Removal
<input type="checkbox"/> HTC Grind for Prep	<input type="checkbox"/> Saw Cut Keyway(s)
<input type="checkbox"/> Acid Etch <input type="checkbox"/> Normal <input type="checkbox"/> Mild	<input type="checkbox"/> Rinse with Water
<input type="checkbox"/> Scrub with Ardition	<input type="checkbox"/> Walk Behind Scrub
<input type="checkbox"/>	
<input type="checkbox"/>	
<input type="checkbox"/>	
<input type="checkbox"/>	
<input type="checkbox"/>	

<input checked="" type="checkbox"/> Primer <input type="checkbox"/> Membrane FLORORCK 4700
<input type="checkbox"/> Overlay System _____ " avg depth
By: _____
<input checked="" type="checkbox"/> Quartz System <input type="checkbox"/> Single <input checked="" type="checkbox"/> Double
<input type="checkbox"/> Decorative Flake System
By: FLOROCK
<input type="checkbox"/> Polishing System By: _____
of Steps: _____ up to _____ Grit Level
<input type="checkbox"/> Resin Polish <input type="checkbox"/> Salt and Pepper <input type="checkbox"/> Large Aggregate
<input checked="" type="checkbox"/> 6500 MEMBRANE 80' GAL 20 MIL
<input checked="" type="checkbox"/> 4805 BROADCAST COATS & GROUT
<input checked="" type="checkbox"/> MC100 URETHANE TOPCOAT
<input type="checkbox"/>
<input checked="" type="checkbox"/> 148 MIL SYSTEM
<input type="checkbox"/> Clear <input checked="" type="checkbox"/> Color OF CHOICE
<input type="checkbox"/> Spray _____ Coats
<input checked="" type="checkbox"/> Hand Apply _____ Coats

A) Prep/Misc/Coating (per above):	3558 sq ft @	\$15.120	per sq ft	\$53,796.96
B) <input type="checkbox"/> Cove 0" <input type="checkbox"/> Chamfer	0 lin ft @	\$0.000	per lin ft	\$0.00
C) 4" YELLOW Lines <input type="checkbox"/> Sprayed <input checked="" type="checkbox"/> Hand Applied	190 lin ft @	\$15.470	per lin ft	\$2,939.30
D) Underseal with	0 lin ft @	\$0.000	per lin ft	\$0.00
E) <input type="checkbox"/>				\$0.00
F) <input type="checkbox"/>				\$0.00
G) <input type="checkbox"/>				\$0.00
H) <input type="checkbox"/>				\$0.00
I) <input type="checkbox"/>				\$0.00
J) <input type="checkbox"/>				\$0.00
K) <input type="checkbox"/>				\$0.00

CONSTRUCTION JOINTS / SAW CUTS - Prepare and Install to Manufacturer Specifications...

<input type="checkbox"/> Constr. Joints	x	fill with:	0 lin ft @	\$0.000	per lin ft	\$0.00
<input type="checkbox"/> Saw Cuts	x	fill with:	0 lin ft @	\$0.000	per lin ft	\$0.00
<input type="checkbox"/> Perimeter	x	fill with:	0 lin ft @	\$0.000	per lin ft	\$0.00
<input type="checkbox"/> Diamonds	x	fill with:	0 lin ft @	\$0.000	per lin ft	\$0.00
<input type="checkbox"/>						\$0.00
<input type="checkbox"/>						\$0.00
<input type="checkbox"/>						\$0.00

Note: Caulking prior to manufacturer's specs may result in separation of joint sealant on either side or down the middle due to natural shrinkage of new concrete. See separate manufacturer's guidelines enclosed.

CRACK REPAIR - Rout and Sand or Grind to Grade

<input type="checkbox"/> Fill with	0 lin ft @	\$0.000	per lin ft	\$0.00
<input type="checkbox"/> Patch Miscellaneous	0 Holes @	\$0.000	per hole	\$0.00

JOINT RE-CONSTRUCTION

<input type="checkbox"/> Saw Cut	<input type="checkbox"/> Break Out				
<input type="checkbox"/> Fill with	0 lin ft @	\$0.000	per lin ft	\$0.00	
<input type="checkbox"/>				\$0.00	

FOOTAGES ARE APPROXIMATE FOR BIDDING AND WILL BE FIELD MEASURED AT TIME OF SAID WORK...

<input checked="" type="checkbox"/> To be completed in	1 phase(s),	10 day(s) per phase.	Add	0 day(s) for caulking.
<input checked="" type="checkbox"/> Price based on	<input checked="" type="checkbox"/> Weekday	<input type="checkbox"/> Weekend		
<input type="checkbox"/> mastic must be tested for asbestos with report prior to job start				
<input type="checkbox"/> 240/480 volt 3-phase power required onsite or add			per day for generator rental	

TERMS OF PAYMENT - Net 30 Days, 1.5% will be added to invoice after 30 days if payment in full is not received.

0% discount if payment, in full, is received within (5) working days of completion of said work.

Other Information:

NOTICE: This proposal is not valid until acceptance copy is signed and returned certifying your acceptance of the terms and conditions outlined in the "General Conditions of Proposal", regardless of and in addition to other contracts/purchase orders.

No verbal agreements either implied or expressed take precedence over this written proposal.

Accepted:  Date: 5/5/22 Brian Simpson